



### Features

#### NEW CLS: 18" x 4' Working Area

- 150 PSIG @ 450 Deg. F
- EnVision PLC Controls
- External Insulation
- 2 - Thermocouples
- 2 - Vacuum Lines (source/sensing)
- Vacuum Pump and Manifold Included
- Air Compressor, 5hp, 175 psig, 80 gal tank
- 3-Day On-Site Start-Up and Training
- 24 hour Technical Support

Approx. Lead Time: 20 - 24 Weeks

#### NEW CLS: 3' x 4' Working Area

- 150 PSIG @ 450 Deg. F
- EnVision PLC Controls
- External Insulation
- 10 - Thermocouples
- 5 - Vacuum Lines (source/sensing)
- Vacuum Pump and Manifold Included
- Optional Chamber Cart
- 3-Day On-Site Start-Up and Training
- 24 Hour Technical Support

Approx. Lead Time: 20 - 24 weeks

#### NEW CLS: 5' x 10' Working Area

- 200 PSIG @ 450 Deg. F
- EnVision PLC Controls
- INTERNAL Insulation
- 10 - Thermocouples
- 10 - Vacuum Lines
- Vacuum Pump and Manifold Included
- Optional Cooling Tower
- 3-Day On-Site Start-Up and Training
- 24 Hour Technical Support

Approx. Lead Time: 24 - 28 Weeks

• Aerospace • Motorsports • Nuclear • Ballistics • Concrete • Glass •

#### Contact Us:

1278 Hwy 461  
Somerset, KY 42503  
Toll Free: 800-414-4231  
Direct: 606-677-2616  
Fax: 606-676-9157  
Web: <http://www.bondtech.net>  
Email: [elsabrown@earthlink.net](mailto:elsabrown@earthlink.net)

